



Two-Step Multi-Physics Analysis of an Annular Linear Induction Pump for Fission Power Systems

Steven M. Geng and Terry V. Reid
Glenn Research Center, Cleveland, Ohio

NASA STI Program . . . in Profile

Since its founding, NASA has been dedicated to the advancement of aeronautics and space science. The NASA Scientific and Technical Information (STI) Program plays a key part in helping NASA maintain this important role.

The NASA STI Program operates under the auspices of the Agency Chief Information Officer. It collects, organizes, provides for archiving, and disseminates NASA's STI. The NASA STI Program provides access to the NASA Technical Report Server—Registered (NTRS Reg) and NASA Technical Report Server—Public (NTRS) thus providing one of the largest collections of aeronautical and space science STI in the world. Results are published in both non-NASA channels and by NASA in the NASA STI Report Series, which includes the following report types:

- **TECHNICAL PUBLICATION.** Reports of completed research or a major significant phase of research that present the results of NASA programs and include extensive data or theoretical analysis. Includes compilations of significant scientific and technical data and information deemed to be of continuing reference value. NASA counter-part of peer-reviewed formal professional papers, but has less stringent limitations on manuscript length and extent of graphic presentations.
- **TECHNICAL MEMORANDUM.** Scientific and technical findings that are preliminary or of specialized interest, e.g., “quick-release” reports, working papers, and bibliographies that contain minimal annotation. Does not contain extensive analysis.
- **CONTRACTOR REPORT.** Scientific and technical findings by NASA-sponsored contractors and grantees.
- **CONFERENCE PUBLICATION.** Collected papers from scientific and technical conferences, symposia, seminars, or other meetings sponsored or co-sponsored by NASA.
- **SPECIAL PUBLICATION.** Scientific, technical, or historical information from NASA programs, projects, and missions, often concerned with subjects having substantial public interest.
- **TECHNICAL TRANSLATION.** English-language translations of foreign scientific and technical material pertinent to NASA's mission.

For more information about the NASA STI program, see the following:

- Access the NASA STI program home page at <http://www.sti.nasa.gov>
- E-mail your question to help@sti.nasa.gov
- Fax your question to the NASA STI Information Desk at 757-864-6500
- Telephone the NASA STI Information Desk at 757-864-9658
- Write to:
NASA STI Program
Mail Stop 148
NASA Langley Research Center
Hampton, VA 23681-2199



Two-Step Multi-Physics Analysis of an Annular Linear Induction Pump for Fission Power Systems

Steven M. Geng and Terry V. Reid
Glenn Research Center, Cleveland, Ohio

Prepared for the
14th International Energy Conversion Engineering Conference
sponsored by the American Institute of Aeronautics and Astronautics
Salt Lake City, Utah, July 25–27, 2016

National Aeronautics and
Space Administration

Glenn Research Center
Cleveland, Ohio 44135

Acknowledgments

This work was performed for the NASA Enabling Technology Development and Demonstration Program/Fission Power Systems Project.

This report is a formal draft or working paper, intended to solicit comments and ideas from a technical peer group.

This report contains preliminary findings, subject to revision as analysis proceeds.

Trade names and trademarks are used in this report for identification only. Their usage does not constitute an official endorsement, either expressed or implied, by the National Aeronautics and Space Administration.

Level of Review: This material has been technically reviewed by technical management.

Available from

NASA STI Program
Mail Stop 148
NASA Langley Research Center
Hampton, VA 23681-2199

National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
703-605-6000

This report is available in electronic form at <http://www.sti.nasa.gov/> and <http://ntrs.nasa.gov/>

Two-Step Multiphysics Analysis of an Annular Linear Induction Pump for Fission Power Systems

Steven M. Geng and Terry V. Reid
National Aeronautics and Space Administration
Glenn Research Center
Cleveland, Ohio 44135

Abstract

One of the key technologies associated with fission power systems (FPSs) is the annular linear induction pump (ALIP). ALIPs are used to circulate liquid metal fluid for transporting thermal energy from the nuclear reactor to the power conversion device. ALIPs designed and built to date for FPS project applications have not performed up to expectations. A unique, two-step approach was taken toward the multiphysics examination of an ALIP using ANSYS Maxwell 3D and ANSYS Fluent (ANSYS, Inc., Canonsburg, PA). This multiphysics approach was developed so that engineers could investigate design variations that might improve pump performance. Of interest was to determine if simple geometric modifications could be made to the ALIP components with the goal of increasing the Lorentz forces acting on the liquid metal fluid, which in turn would increase pumping capacity. The multiphysics model first calculates the Lorentz forces acting on the liquid metal fluid in the ALIP annulus. These forces are then used in a computational fluid dynamics simulation as (a) internal boundary conditions and (b) source functions in the momentum equations within the Navier-Stokes equations. The end result of the two-step analysis is a predicted pump pressure rise that can be compared with experimental data.

Nomenclature

A_{surface}	surface area
B	magnetic flux density
C_1	activation constant for continuity equation mass source term
C_2	activation constant for momentum equation stress tensor
C_3	activation constant for momentum equation body force source term
C_4	activation constant for energy equation source term
D	displacement field
E	electric field
\vec{F}	body force source term
F_L	Lorentz force
G	internal energy field
g	gravity
H	magnetic field
\bar{I}	unit tensor
J	current distribution
k	thermal conductivity
μ	dynamic viscosity
P	pressure
ρ	fluid mass density

ρ^{charge}	electric charge density
S_m, Sh	mass source and energy source terms
σ	electrical conductivity
$\bar{\tau}$	stress tensor
T	temperature
t	time
\vec{v}	velocity field
Vol_{slug}	slug volume

1.0 Introduction

Fission power system (FPS) technology is being developed for use on the surface of the Moon, Mars, or other moons and planets of our solar system. FPSs are capable of providing good performance at any location, including those near the poles or other permanently shaded regions, and offer the capability to provide on-demand power at any time, even at long distances from the Sun. Fission-based systems also offer the potential for outposts, crew, and science instruments to operate in a power-rich environment.

One of the key technologies associated with the FPS is the annular linear induction pump (ALIP) used to circulate the liquid metal fluid that transports thermal energy from the nuclear reactor to the power conversion device. In 2010, an ALIP developed by the Idaho National Laboratory (INL) was tested under representative space-reactor thermal operating conditions at the NASA Marshall Space Flight Center to quantify the pump's performance (Ref. 1). The measured performance was below expectations. Illustrations of the ALIP pump are shown in Figure 1. Marshall conducted performance testing of the ALIP using their test circuit shown in Figure 2. The test circuit consists of the ALIP, an induction heater, a throttling valve, an electromagnetic flow meter, and a gaseous nitrogen to NaK heat exchanger. The throttling valve is located downstream of the ALIP (in the test circuit) so that the flow resistance could be varied.

In 2012, NASA Glenn Research Center developed a magnetostatic finite element model of the ALIP to gain a better understanding of its functionality, and to independently evaluate design variations that might have contributed to the performance shortfall (Ref. 2). In 2015, the ALIP model was upgraded to a three-dimensional transient magnetic analysis, which dramatically simplified the post-processing of the model predictions. The magnetic model takes advantage of ALIP symmetry to reduce computation time.




Figure 1.—Two views of annular linear induction pump (ALIP). (Illustrations courtesy of Idaho National Laboratory; used with permission.)




Figure 2.—Annular linear induction pump (ALIP) test circuit. (a) Schematic. (b) Photograph. (Courtesy of NASA Marshall Space Flight Center.)

A full three-dimensional computational fluid dynamics (CFD) model was recently created of the ALIP that when used in combination with the magnetic model, could generate pressure rise and flow rate predictions for comparison with the experimental data. Symmetry is not assumed in the CFD model due to the inhomogeneous pressure distribution in the NaK flow annulus.

The multiphysics ALIP model was validated against experimental data, then used to generate performance predictions. This paper presents a discussion of the multiphysics (three-dimensional transient magnetic and CFD) model of the ALIP, a comparison of model predictions versus experimental data, and a discussion of several design variations that could potentially have a positive impact on pump performance.

2.0 Fission Power System Reference Concept Demonstration

Power is an important consideration when planning the exploration of planetary surfaces. Nuclear power is an enabling option for locations in the solar system where sunlight is limited. A Fission Surface Power preliminary reference concept (Ref. 3) was developed, and a full-scale one-quarter power Technology Demonstration Unit (TDU) was built and tested (Ref. 4) to demonstrate the system level of readiness (see Figure 3). An ALIP was used to circulate NaK-78 through the loop of the TDU to transfer thermal energy from the reactor core simulator to a 12-kWe free-piston Stirling power convertor. The 12-kWe Stirling convertor comprises two dual-opposed 6-kWe Stirling engines. The core simulator heats the NaK to 550 °C, and as the heated NaK circulates through the loop, the thermal energy is transferred to the Stirling convertor through a pair of heat exchangers. The ALIP must impart a sufficient pressure rise on the NaK fluid to overcome the pressure drop loss produced by the loop components (piping, core simulator, and heat exchangers).

3.0 Analysis Description

A multiphysics two-step approach was taken to model the ALIP used in the TDU test. The following section describes the governing equations used by each solver in the various analyses. The application of these equations occurred in the magnetic and fluid flow solvers (ANSYS Maxwell and ANSYS Fluent (ANSYS, Inc., Canonsburg, PA)). The conditions that were chosen for the calculations were based on data from experimental testing of the ALIP by the NASA Marshall Space Flight Center.




Figure 3.—Fission power system (FPS) Technology Demonstration Unit (TDU). (a) Test article. (b) Computer-aided design (CAD) model.

3.1 Magnetic Field Analysis

The ANSYS Maxwell software was used to create a transient magnetic model of the ALIP. The Maxwell software basically solves the differential form of Maxwell's equations. The following equations include Faraday's law of induction (Eq. (1)), Gauss's law for magnetism (Eq. (2)), Ampere's law (Eq. (3)), and Gauss's law for electricity (Eq. (4)).

$$\nabla \times E = -\frac{\partial B}{\partial t} \quad (1)$$

$$\nabla \cdot B = 0 \quad (2)$$

$$\nabla \times H = J + \frac{\partial D}{\partial t} \quad (3)$$

$$\nabla \cdot D = \rho_{\text{charge}} \quad (4)$$

The Maxwell transient field simulator calculates the time-domain magnetic fields in three dimensions. The source of the magnetic fields is the three-phase current flowing through the 12 ALIP coils. The transient field simulator solves for the magnetic field (H), current distribution (J), and the magnetic flux density (B). Derived quantities such as Lorentz force acting on the NaK fluid, winding flux linkage, and induced voltage/current in the NaK fluid are calculated from the basic field equations.

3.2 Fluid Flow Field Analysis

The flow field analysis involves the solution of the Navier Stokes equations, which include conservation of mass, momentum, and energy. The conservation of mass (Eq. (5)) and conservation of momentum (Eq. (6)) are

$$\frac{\partial \rho}{\partial t} + \nabla * (\rho \vec{V}) = C_1 S_m \quad (5)$$

$$\frac{\partial(\rho \vec{V})}{\partial t} + \nabla * (\rho \vec{V} \vec{V}) = -\nabla P + C_2 \nabla * (\bar{\bar{\tau}}) + \rho \vec{g} + C_3 \vec{F} \quad (6)$$

The stress tensor, $\bar{\bar{\tau}}$, is given by

$$\bar{\bar{\tau}} = \mu \left[(\nabla \vec{V} + \nabla \vec{V}^T) - \frac{2}{3} \nabla * \vec{V} \vec{I} \right] \quad (7)$$

where μ is the molecular viscosity, I is the unit tensor, and the second term on the right-hand side is the effect of volume dilation. The energy Equation (8) is defined by

$$\frac{\partial(\rho G)}{\partial t} + \nabla * (\vec{V}(\rho G + p)) = \nabla(k \nabla T + C_2 (\bar{\bar{\tau}} * \vec{V})) + C_4 S_h \quad (8)$$

In the energy equation, k is the thermal conductivity, while the three terms on the right-hand side of the equation represent energy transfer due to conduction, viscous dissipation, and source/sink terms. It should be noted that there are source terms on the right-hand side of each of the above equations (Eqs. (5), (6), and (8)). Their coefficients are C_1 for mass, C_2 and C_3 for momentum, and C_4 for energy sources. These values are either 0 or 1, depending on which source terms are used during the analysis. Two different approaches to solving the fluid flow problem were evaluated. The first approach was assumed to be incompressible and inviscid; $C_1 = C_2 = C_3 = C_4 = 0$ (no viscous or source terms were used). In the second approach, the Boussinesq hypothesis (density changes due to buoyancy, which are accounted for in the realizable k - ϵ turbulence model) was used so that $C_1 = C_4 = 0$ and $C_2 = C_3 = 1$ (viscous and source terms used). These constants are the basis for how the Lorentz forces from the magnetic analysis were handled relative to the CFD problem. This will be discussed in greater detail in the following section.

4.0 Model Description

ANSYS Design Modeler, Meshing, Maxwell, and Fluent (ANSYS, Inc., Canonsburg, PA) were used to perform these analyses. The analyses were performed in series.

4.1 Magnetic Field Model

The three-dimensional transient model is shown in Figure 4. The components modeled include the Hiperco 50 torpedo, 2 Hiperco 50 lamination half stacks, 12 copper coils, and the NaK-78 fluid contained within the body of the ALIP pump discretized as 25 individual segments or slugs. The three-dimensional transient model takes advantage of symmetry. Only a 60° wedge of the ALIP was modeled to reduce computation time. Although the model was useful for calculating the magnetic forces acting on the liquid metal contained within the ALIP, the predictions could not be compared directly with the experimental data.

Three-phase electrical power input is required to establish a moving magnetic wave down the annulus of the ALIP. Current amplitude and frequency are inputs for the model. Figure 5 shows an example of the model input to simulate a 36-Hz, 18-A (peak) operating condition. To facilitate numerical stability in the transient solver, the current is ramped up from zero to full current within two electrical cycles. Note that the current amplitudes of the three-phase power were not equal. During testing at Marshall, it was




Figure 4.—Three-dimensional transient model of annular linear induction pump (ALIP).




Figure 5.—Three-phase current ramp-up at 36 Hz.

determined that for any given operating condition, the current in phase B (I_B) was always greatest, while the phase A current (I_A) was always the smallest with the phase C current (I_C) falling in between. The current imbalance between the three phases was maintained for all model predictions for comparison with the Marshall data.

The transient magnetic model of the ALIP calculates the Lorentz forces and B-fields acting on each of the 25 slugs of NaK-78 fluid, for 5 complete electrical cycles (10 magnetic cycles). The 25 slugs of NaK fluid are shown in Figure 6. Slugs of NaK located adjacent to the stator poles are labeled beginning with the letter “P.” Figure 7 and Figure 8 show examples of the axial and radial Lorentz forces acting on a NaK slug adjacent to one of the stator poles (P2) over one electrical cycle, respectively. Note that the negative axial forces shown in Figure 7 oppose the NaK fluid flow in the pump. The radial forces shown in Figure 8 are always directed radially inward.

Figure 9 and Figure 10 show the peak Lorentz forces in the axial and radial directions for each NaK slug in the ALIP annulus over one electrical cycle. It is interesting to note that the majority of the axial force acting on the NaK is in alignment with the fluid flow direction. However, there are times when the axial force in portions of the pump oppose the fluid flow. Figure 10 shows that the radial forces acting on each NaK slug are always directed radially inward, and are generally larger than the axial forces. Based on these results, it can be concluded that the total (axial + radial) Lorentz forces acting on the NaK fluid are, in general, aimed more in the radially inward direction than in the axial direction.




Figure 6.—Section view of annular linear induction pump (ALIP) defining NaK slugs.




Figure 7.—Axial Lorentz forces acting on NaK slug P2.




Figure 8.—Radial Lorentz forces acting on NaK slug P2.




Figure 9.—Peak Lorentz forces acting on NaK slugs in axial direction.




Figure 10.—Peak Lorentz forces acting on NaK slugs in radial direction. ALIP is annular linear induction pump.




Figure 11.—Torpedo B-field magnitude at time = 0.134722 s. (a) B-field prediction for annular linear induction pump (ALIP) configured with hollow torpedo (baseline geometry). (b) B-field prediction for ALIP configured with solid torpedo.

The prototypic ALIP pump used in the TDC test utilizes a hollow torpedo. The transient magnetic analysis was used to evaluate the torpedo to determine if there was sufficient material to carry the magnetic fields. Figure 11(a) shows the B-field magnitude in the torpedo body at an instant in time. Assuming a torpedo temperature of 550 °C, Figure 11(a) shows three locations (circled areas) where mild saturation may be occurring. According to the Glenn Hiperco 50 BH measurements (shown in Figure 12), Hiperco 50 tends to saturate at about 1.8 T at 550 °C. The magnetic analysis was then repeated assuming a solid torpedo. Figure 11(b) shows that the solid torpedo can eliminate the areas of saturation.

4.2 Computational Fluid Dynamics Model

The geometry of the ALIP CFD model is shown in Figure 13. The CFD model includes the torpedo struts (supports torpedo in pump body as shown in Figure 13), and the slugs of NaK in the annulus. The solid torpedo volume was removed from the constant diameter midsection, which forms the annulus. Inside the annulus are 13 NaK slugs located adjacent to the stator poles, and 12 NaK slugs located adjacent to the coils.




Figure 12.—BH data for Hipercro 50 at various temperatures.




Figure 13.—Annular linear induction pump (ALIP) computational fluid dynamics (CFD) model.




Figure 14.—Orientation of NaK slugs.

Figure 14 shows the target surfaces in the CFD model where Lorentz forces (produced by the three-dimensional transient magnetic analysis model) are applied. As mentioned previously, two different CFD approaches were examined. In approach 1, the results of the magnetic transient analysis are applied on two surfaces (axial and radial) for each of the 25 slugs of the CFD model. All of these transient force profiles are applied to the NaK in the annulus of the CFD model simultaneously, and calculations are performed until the CFD solution is time periodic (typically within a range of 5 to 10 cycles). In approach 2, the Lorentz forces are added to the source terms in the momentum equation.

The difference between the strategies is the method in which the Lorentz forces are applied to the NaK slugs. The equations that define the Lorentz forces are

$$\vec{F}_L = \vec{J} \times \vec{B} \quad (9)$$

where

$$\vec{J} = \sigma [\vec{E} + (\vec{v} \times \vec{B})] \quad (10)$$

The variable J is the current distribution and B is the magnetic field. In approach 1, the Lorentz forces (F_L) are converted to pressures by dividing force by the area of application ($P \sim F_L/A_{\text{surface}}$). The pressures acting on the NaK slug surfaces are updated every time step. Approach 2 involves adding the Lorentz forces as body force source terms ($\vec{F} \sim F_L/Vol_{\text{slug}}$) in the momentum equations (Ref. 5). Both strategies were evaluated in terms of ALIP pressure rise, and it was determined that approach 2 provided results that better matched the measured data. Therefore, the results and conclusions presented in this paper are based on the approach 2 strategy.

During the beginning stages of the calculations, consideration was given to the throttling valve, which is a part of the ALIP test circuit (originally shown in Figure 2). A closeup view of the valve is shown in Figure 15. Its actual location in the ALIP test circuit is 15 to 20 diameters downstream of the ALIP exit and beyond a 90° bend. This valve provides a downstream resistance that affects both the operating pressure and the flow rate. Detailed measurements were made to determine the relationship between valve position and NaK flow rate. A plot of NaK flow rate with respect to valve position is shown in Figure 16.




Figure 15.—Throttling valve used in the annular linear induction pump (ALIP) test circuit. (a) Rendering. (b) Photograph. (Courtesy of NASA Marshall Space Flight Center.)




Figure 16.—Characteristic flow curve of custom throttling valve used in the annular linear induction pump (ALIP) test circuit. (Courtesy of NASA Marshall Space Flight Center.)




Figure 17.—Partially closed gate valve (91.5 percent closed) in the computational domain. (a) Model. (b) Predicted velocity vectors.




Figure 18.—Baseline predictions (60 gpm) with and without downstream valve.

Calculations were performed assuming approach 1 for the ALIP test circuit configured both with and without the valve. When in place, it is required that the valve be 91.5 percent closed to produce a volumetric flow rate of ~60 gpm. The valve placement and resulting predicted NaK fluid velocities are shown in Figure 17. For these predictions, the valve was placed close to the exit of the computational domain to minimize the size of the mesh. However, when generating predictions with the valve in place, the separated flow downstream of the valve created an unsettled flow field that propagated out of the exit boundary in a nonuniform manner, which was deemed undesirable. The calculations were repeated with the valve removed, and the results were compared in Figure 18. It was discovered that the inclusion or omission of the valve in the model had no impact on the predicted pressure rise; the valve only affected the predicted ALIP inlet and outlet pressures. Unfortunately, including the valve in the model required far more computation time to reach a converged solution. As a result, it was decided to omit the valve from the simulations.

5.0 Results

As mentioned in Section 4.2, two CFD approaches were evaluated. Approach 1 (180° model) was used for only the baseline case. Once it was determined that the predicted pressure rise using this approach was about 15 percent lower than the measured value, it was decided to try approach 2. However, approach 2 (180° model) overpredicted the baseline measured data by 20 percent. This computational overprediction was also observed by Maidana (Ref. 5) when using reduced (<360°) CFD models that

assumes symmetry. The approach 2 full 360° model was considered the most accurate, and as a result, was used to generate the predictions shown in this paper.

Since the multiphysics simulation is computationally time intensive (it takes about a week to simulate a single test condition), a single flow rate (60 gpm) was chosen for code validation. At the selected validation point, the three-dimensional multiphysics model predicted a pressure rise of 22.0 kPa (3.2 psi), which was just slightly below (within 3 percent) of the measured value of 22.6 kPa (3.28 psi). The three-dimensional multiphysics model was then used to predict the pump performance over a range of NaK flow rates as shown in Figure 19 and Table I. The predictions were in good agreement with the experimental data at the mid- to high-NaK flow rates. The agreement was not quite as good at the low NaK flow condition. The reason for this discrepancy may be due to the turbulence model being used in the CFD analysis. The NaK flow may not be fully turbulent at the low flow conditions. In addition, researchers have reported (Ref. 6) that all two-equation turbulence models (such as $k-\epsilon$ and $k-\omega$ turbulence models) experience a reduction in accuracy in the presence of “large” adverse pressure gradients. They tend to underpredict separation of the boundary layers due to this adverse pressure gradient. This leads to an underestimation of the effects of viscous-inviscid interaction, which generally produces a performance estimate that is too optimistic for aerodynamic bodies. It is possible to live with this error if verification and validation indicates that it is not too high, otherwise a more robust turbulence model may be needed.

The multiphysics model was then used to explore ALIP geometric variations in an attempt to improve pump performance. At the time of this writing, only one design variation was completely modeled: a solid torpedo was substituted for the baseline hollow torpedo. When the hollow torpedo is replaced with a solid torpedo, the predicted pump pressure rise is 16 percent larger. This suggests that replacing the hollow torpedo with a solid torpedo would result in a modest performance improvement due to an increase in saturation margin. Another design variation that would be interesting to explore would be to substitute a




Figure 19.—Comparison of measured and predicted annular linear induction pump (ALIP) data (100 V, 18 A, and 36 Hz). (Measured data courtesy of NASA Marshall Space Flight Center.)

TABLE I.—TEST MATRIX SUMMARY

Torpedo configuration	Flow rate		Measured ΔP		Predicted ΔP		Percent difference
	gpm	Liter/s	psi	kPa	psi	kPa	
Hollow	28.8	1.82	6.51	44.87	7.45	51.37	14.5
	60.0	3.79	3.28	22.61	3.20	22.03	−2.6
	82.9	5.23	0.40	2.76	0.38	2.64	−4.4
Solid	60.0	3.79	-----	-----	3.80	26.19	^a 15.8

^aPercent difference relative to measurement recorded for 60 gpm in baseline ALIP (hollow torpedo) configuration.

stepped torpedo for the baseline hollow torpedo. The flow path of the NaK would still be a smooth annulus since the torpedo is encased inside a stainless steel sleeve. The diameter of the torpedo adjacent to the coils would be a little bit smaller than the diameter of the torpedo adjacent to the poles of the stator. The idea here is to encourage the B-field passing through the NaK to flow in a more radial direction, in hopes of better aligning the Lorentz forces with the NaK flow direction. With the prototypic ALIP used in the TDU test, a simple substitution of a stepped torpedo for the hollow torpedo would probably not help since saturation would still be an issue. The whole ALIP pump would need to be redesigned to allow for a larger diameter torpedo to prevent B-field saturation.

6.0 Conclusion

The multiphysics approach described in this paper was found to be in good agreement with the annular linear induction pump (ALIP) experimental data at the mid- to high-flow operating conditions. Further model development is necessary to improve ALIP performance predictions over a wider range of operating conditions. The realizable k - ϵ turbulence model was selected for use in the fluid flow analysis. It is possible that this turbulence model is less accurate at the pressure gradients encountered at the low NaK flow conditions. Several other turbulence models are available. Some effort should be applied toward determining the best turbulence model for use in this application.

Based on the results presented in this paper, the prototypic ALIP performance could potentially be improved by replacing the hollow torpedo with a solid configuration. In future ALIP designs, it might be beneficial to explore the impact of tailoring the torpedo geometry to better align the Lorentz forces with the NaK flow direction. The methods described in this paper may be of value in evaluating future ALIP designs.

References

1. Polzin, K.A., et al.: Performance Testing of a Prototypic Annular Linear Induction Pump for Fission Surface Power. NASA/TP—2010-216430, 2010. <http://ntrs.nasa.gov>
2. Geng, S.M.; Niedra, J.M.; and Polzin, K.A.: Magnetic Analysis of an Annular Linear Induction Pump for Fission Power Systems. Proceedings of the Nuclear and Emerging Technologies for Space, paper 3033, Woodlands, TX, 2012.
3. Fission Surface Power System Initial Concept Definition. NASA/TM—2010-216772, 2010. <http://ntrs.nasa.gov>
4. Briggs, M.H., et al.: Fission Surface Power Technology Demonstration Unit Test Results. Proceedings of the Nuclear and Emerging Technologies for Space 2016, paper 6074, Huntsville, AL, 2016.
5. Maidana, Carlos O.; and Nieminen, Julia E.: Multiphysics Analysis of Liquid Metal Annular Linear Induction Pumps. Proceedings of the Nuclear and Emerging Technologies for Space 2016, abstract 6069, Huntsville, AL, 2016.
6. Bardina, J.E.; Huang, P.G.; and Coakley, T.J.: Turbulence Modeling Validation, Testing, and Development. NASA TM-110446, 1997. <http://ntrs.nasa.gov>

